kapoor and associates

ARCHITECTURE | INTERIOR DESIGN | URBAN DESIGN

100-B. Patliputra Colony. Opp. P & M Mall Near Notre Dame Academy. Patna 800013 Tel/Fax: 0612 - 2267175 / 2275624 E: contact@kapoors.biz | Web: www.kapoors.biz



REF:DAV/04638/2024

September 26th, 2024

<u>DAV PUBLIC SCHOOL, NAWADA</u> SPECIFICATIONS AS PER ESTIMATE

Brief Specifications for DAV Public Schools(for Bihar Zone):

CONCRETE MIX:

THE MINIMUM GRADE OF CONCRETE WHICH CAN BE USED IS M:25 ALL CONSTRUCTION UNDER THIS CONTRACT SHALL BE OF M:25 CONCRETE.

1. **Structure** : Frame Structure generally with a group of under reamed piles, pile

caps or with Open Foundations and tie beams as / standard design. All RCC work to be done in the specified mix, with mixers / vibrators /

etc.

2. **Plinth Height** : 4'-0" from Existing Ground Level / As per Site condition.

3. **Superstructure** : 10" brick walls in C.M 1:6, 5" reinforced brick walls in C.M 1:4.

5" thick brick work to be reinforced with 1 no. 6 dia rod at every 4th layer. In both 10" and 5" thick brick walls, a continuous band of

R.C.C at lintel level to be given.

4. **Roof Height** : 11'-0" Floor to floor, except as specified.

5. **Cement Plaster** : On RCC Surfaces in CM 1:4. On brick surfaces in CM 1:6.

6. **Flooring** : Sand Filling upto Plinth Level, properly watered and rammed

Flat Brick Soling 3" thick PCC 1:3:6 4" thick

in Class Rooms- Kota Stone Flooring

Hall, Common Areas, Green Room, Corridor, Staircases, with Kota

Stone Flooring.

Principal Chamber, Staff Room Office and Waiting areas-Vitrified Tile Flooring(SOMANY / KAJARIA / JOHNSON) double charged

(Soluble Salt tiles shall not be permitted)

Bathroom Flooring to be of Good Quality Ceramic Tiles of size 1'-0" x 1'-0". (Makes as given above)

7. **Dado** : 4'-0" high glazed tiles on both side of the verandahs

.

Toilets to have 5'-0" high glazed tiles in Dado.

8. **Doors** : 35mm thick Phenol Bonded Flush Doors, brand GREENPLY /

CENTURY or ISI Mark made or 38mm thick gambhar doors, with gambhar wood, as per design and details.

9. **Door Choukhats** : Profile-B

10. **Windows** : Steel Glazed Windows.

11. **Painting** : Exterior Acrylic smooth exterior paint from M/s Berger / Asian/

Nerolac on all external surfaces and verandahs. (Min. 2 coats over a

coat of white cement).

Distemper in all Classrooms.

Entrance Hall / Waiting Lobby, Principals Chamber / Office & Staff

room, with J.K.Wall Putty and Acrylic Oil Bound Distemper.

Doors / Windows with 1st quality Synthetic Paint over 1 coat of

Primer.

12. **Plinth Protection** : 2'-6" all around building with 50mm thick cement concrete (1:3:6)

over Brick flat Soling, pointed, etc. as per CPWD Specifications.

Waterproofing in down slab.

13. **Plumbing and Sanitary**: All CPVC Pipes to be of Ashirwad / Astral / Prince / Supreme). (This

includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in

Charge. All GI pipes of Tata.

All SWR Pipes to be 4" dia, PRINCE / SUPREME / FINOLEX All C.P Fittings to be of ESSCO/ARC. No local fittings shall be

allowed.

All urinals / w.c's wash basins to be of CERA / PARRYWARE /

HINDUSTAN, full size

14. **Electrical** : Concealed Wiring for all Electrical Points,

All switches to be of ANCHOR / CONA / KOLORS /

Make

All wires to be of FINOLEX / ANCHOR / Polycab make

•

15 **Stair railing** : M.S Railing

16. **Makes of Materials**: As per attached sheet

17. Measurement of Plinth Area:

This shall be as per DAV Standards, where the area upto the Outer Line of the Columns / Projections shall be measured, if the RCC Roof extends to such areas. If not, only the actual footprint of the columns shall be added to the areas. Areas of chajjas, etc. SHALL NOT be added to plinth areas.

18. **Curing**

It shall be ensured that on any work where "cement" is used, full curing is done for a period of 15 days.

Note: The defect liability period shall be for 12 months after the entire building / the part fully completed and handed over / occupied by the School has been fully completed / occupied and handed over. 10% of the payment of the Contractor shall be retained for a period of 12 months from the date of final finishing / completion / handing over to the School.